

Subdivisional Lines, T.2 N., R.27 E., W. M.

Chains		Feet
46.00	Enter Butter Creek bottom.	
79.45	Enter Butter Creek, at this place it is dry & brs.N.E.	
79.85	The Cor. to Secs. 1, 2, 11 & 12. Soil; on Butter Creek bottom, 1st rate, rich black loam & a little alkali and land level. On E. part it is 3rd rate & rolling.	
	N. on random line bet. Secs. 1 & 2.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.80	Intersect N. Bdy. of Tp., 35 lks. W. of Cor. to Secs. 1, 2, 35 & 36, from which Cor., I run, S.0°15'W. on true line bet. Secs. 1 & 2.	
12.00	Enter Butter Creek bottom.	
40.80	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
80.80	Cor. to Secs. 1, 2, 11 & 12. Land; on Butter Creek bottom, level, 1st & 2nd rate. Remainder rolling & 3rd rate. Oct. 6, 1860.	
	Oct. 7, 1860	
	N. bet. Secs. 34 & 35	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits, & deposited 1 pt. charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 26, 27, 34 & 35, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions. Soil; 2nd & 3rd rate, producing grass. Land; high & rolling.	
	E. on random line bet. Secs. 26 & 35. Var. 20°E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.40	Intersect N. & S. line, 20 lks. S. of Cor. to Secs. 25, 26, 35 & 36, from which Cor., I run S.89°51'W. on true line bet. Secs. 26 & 35.	