

## Subdivisional Lines, T.2 N., R.27 E., W. M.

Chains		Feet
	instructions.	
	Butter Creek, 20 lks. wide.	
40.50	Leave Butter Creek.	
41.24	Enter " "	
42.25	Leave " " , runs N.-N.E.	
80.00	Set post for Cor. to Secs. 21, 22, 27 & 28, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
	Land on Butter Creek, level 1st & 2nd rate- remainder, hilly & 3rd rate.	
<hr/>		
	E. on random line bet. Secs. 22 & 27.	
	Var. 19°35'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.90	Intersect N. & S. line, 33 lks. S. of Cor. to Secs. 22, 23, 26 & 27, from which Cor., I run S. 89°46'W. on true line bet. Secs. 22 & 27.	
39.95	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions. Enter Butter Creek bottom.	
57.10	Butter Creek, 20 lks. wide, runs N.-N.E.; at the intersection it is dry.	
79.90	The Cor. to Secs. 21, 22, 27 & 28. Soil; on bottom , 1st rate & level. Remainder land, hilly soil 3rd rate.	
<hr/>		
	N. bet. Secs. 21 & 22.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
45.00	Trail up Butter Creek, brs. S.-S.W. Leave bottom & enter high land.	
80.00	Set post for Cor. to Secs. 15, 16, 21 & 22, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions. Soil; 1st & 2nd rate. Land; on bottom, level.	