

## Subdivisional Lines, T.2 N., R.27 E., W. M.

Chains		Feet
	N. bet. Secs. 9 & 10.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 9, 10, 3 & 4, in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	
	Soil; 3rd rate, producing grass.	
	Land; rolling.	
<hr/>		
	E. on random line bet. Secs. 3 & 10.	
	Var. 20°5'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.98	Intersect N. & S. line, 5 lks. N. of Cor. to Secs. 2, 3, 10 & 11, from which Cor., I run N.89°58' W. on true line bet. Secs. 3 & 10.	
39.99	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	
79.98	The Cor. to Secs. 3, 4, 9 & 10.	
	Soil; 3rd rate.	
	Land; high & rolling.	
<hr/>		
	N. on random line bet. Secs. 3 & 4.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.56	Intersect N. Bdy. of Tp., 2 lks. W. of Cor. to Secs. 3, 4, 33 & 34, from which Cor., I run S.0°1'W. on true line, bet. Secs. 3 & 4.	
26.50	Road from the Dalles to Walla Walla, brs. E.-N.E.	
40.56	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	
80.56	The Cor. to Secs. 3, 4, 9 & 10.	
	Soil; 3rd rate.	
	Land; high & rolling.	
	Oct. 8, 1860.	
<hr/>		
General Description.		
<hr/>		
This Tp. is adapted principally to grazing purposes, produc-		