

T. 2 N., R. 28 E.

Chains	N. 89° 30' W., on true line between secs. 6 and 31. Var. 20° 45' East.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth &c as per instructions.
78.36	The corner to Townships 2 and 3, North of Ranges 27 and 28 East. Var. 20° East.
	Land, level, 1st rate. October 4, 1859.
General Description	
The quality of land in this Township is generally 1st rate level prairie covered with grass. This Township will admit of a large settlement and should, therefore, be subdivided.	
Subdivisions of T. 2 N., R. 28 E. Surveyed by David P. Thompson under contract No. 83 Dated July 22, 1859.	
	North between secs. 35 and 36.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth &c as per instructions.
80.00	Set post for corner to secs. 25, 26, 35 and 36 in mound of earth &c as per instructions. Land, gently rolling. Soil, good, 2nd rate.
	East on random line between secs. 25 and 36.
40.00	Set post for temp. $\frac{1}{4}$ sec. corner.
79.70	Intersect East boundary, 70 links North of sec. corner. N. 89° 30' W., on true line, between secs. 25 and 36.
39.85	Set post for $\frac{1}{4}$ sec. corner in mound of earth &c as per instructions.
79.70	The corner to secs. 30, 31 25 and 36. Land, gently rolling. Soil, 2nd rate.