

Subdivisions of T. 2 N., R. 28 E.

Chains	
	instructions.
79.60	The post to secs. 1, 2, 11 and 12. Land, level. Soil, 1st rate.
	North on random line between secs. 1 and 2. Var. 20° East.
40.00	Set post for temp. $\frac{1}{4}$ sec. corner.
80.70	Intersect North boundary, 60 links East of sec. corner. S. 26' East, on true line, between secs. 1 and 2.
40.70	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.70	The corner to secs. 1, 2, 11 and 12. Land, level. Soil, 1st rate.
	October 5, 1859.
	North between secs. 34 and 35.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.00	Set post for corner to secs. 26, 27, 34 and 35 in mound of Earth &c as per instructions. Land, gently rolling. Soil, good, 2nd rate.
	East on random line between secs. 26 and 35.
40.00	Set post for temp. $\frac{1}{4}$ sec. corner.
80.00	Intersect N. and S. line, 71 links North of sec. corner. N. 89° 30' W., on true line, between secs. 26 and 35.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.00	The corner to secs. 26, 27 34 and 35. Land, gently rolling. Soil, 1st rate.
	North between secs. 26 and 27.