

## Subdivisions of T. 2 N., R. 28 E.

Chains	
40.00	Set post for temp. $\frac{1}{4}$ sec. corner.
79.50	Intersect N. and S. line, 28 links North of sec. corner. N. $89^{\circ} 48'$ W., on true line, between secs. 2 and 11.
20.00	Trail bears N.E, S.W.
39.75	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
79.50	The corner to secs. 2, 3, 10 and 11. Land, gently rolling. Soil, good, 2nd rate.
North on random line between secs. 2 and 3. Var. $20^{\circ} 20'$ East.	
40.00	Set post for temp. $\frac{1}{4}$ sec. corner.
80.81	Intersect North boundary of Township, 56 links East of sec. corner. S. $0^{\circ} 24'$ E. on true line between secs. 2 and 3.
40.81	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.81	The corner to secs. 2, 3, 10 and 11. Land, level. Soil, 1st rate.  October 6, 1859.
North between secs. 33 and 34.	
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.00	Set post for corner to secs. 27, 28, 33 and 34 in mound of Earth &c as per instructions. Land, gently rolling. Soil, 1st rate.
East on random line between secs. 27 and 34.	
40.00	Set temp. $\frac{1}{4}$ sec. corner.
79.94	Intersect N. and S. line at sec. corner. West on true line between secs. 27 and 34.
34.50	Indian Trail bears N.E. and S. W.