

## Subdivisions of T. 2 N., R. 29 E.

Chains	
	instructions.
80.00	Set post for corner to secs. 1, 2, 11 and 12 in mound of Earth &c as per instructions. Land, gently rolling. Soil, good, 2nd rate.
	East, on random, between secs. 1 and 12.
40.00	Set post for temp. $\frac{1}{4}$ sec. corner.
80.45	Intersect East boundary, 18 links South of sec. corner. S. $89^{\circ} 52'$ W., on true line, between sec. 1 and 12.
25.00	Ravine bears N. and S.
40.22	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.45	The corner to secs. 1, 2, 11 and 12. Land, good, 2nd rate, gently rolling.
	North, on random line, between secs. 1 and 2. Var. $19^{\circ} 30'$ East.
40.00	Set post for temp. $\frac{1}{4}$ sec. corner.
79.65	Intersect North boundary, 35 links West of sec. corner. S. $15'$ W., on true line, between sec. 1 and.
39.65	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
79.65	The corner to secs. 1, 2, 11 and 12. Land, gently rolling. Soil, good, 2nd rate.
	September 5, 1859.
	North between secs. 34 and 35.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.00	Set post for corner to secs. 26, 27, 34 and 35 in mound of Earth &c as per instructions. Land, gently rolling. Soil, 1st rate.