

1

Guide Meridian between Ranges 30 & 31 E.  
 Surveyed by David P. Thompson, under  
 Contract No. 81. dated July 8, 1859.

Chains	7th Mile.
	North between Ranges 31 & 36 E.
	Variation 18° 15' East.
40.00	Set post for 1/4 Sec. corner and build mound of earth with pits, trench &c., as per instructions.
80.00	Set post for corner to Secs. 30, 31, 25 & 36 and build mound of earth with pits, trench &c., as per instructions.
	Land, gently rolling, grass hills.
	Soil, 2nd rate.
	August 7th, 1859.

	8th Mile.
	North between Secs. 25 & 30.
	Variation 19° 40' East.
40.00	Set post for 1/4 Sec. corner and build mound of earth with pits, trench & c., as per instructions.
	Descend hill.
80.00	Set post for corner to Secs. 24, 25, 19 & 30 and build mound of stone.
	Land, gently sloping to the north.
	Soil, 2nd rate.
	August 7th, 1859.

	9th Mile.
	North between Secs. 19 & 24.
	Variation 22' East.
40.00	Set post for 1/4 Sec. corner and build mound of stone.
80.00	Set post for corner to Secs. 18, 19, 13 & 24 and build mound of earth with pits, trench &c., as per instructions.
	Land, gently sloping to the north.
	Soil, 2nd rate.
	August 7th, 1859.