

## Guide Meridians between Ranges 30 &amp; 31 E.

Chains	
80.00	<p>Set post for Township Nos. 2 &amp; 3 North of Ranges 30 &amp; 31, East and build a mound of earth with pits, trench &amp;c., as per instructions.</p> <p>Top of hill.</p> <p>Land, gently sloping.</p> <p>Soil, 2nd rate.</p> <p>Note: The quality of the land in Township No. 2 North of Ranges 30 &amp; 31 East is generally good, 2nd rate. There is some 1st rate bottom land on the Umatilla River, (which runs through the North part of each township), the banks of which are covered with a heavy growth of cotton wood and birch timber, usually about 20 chains wide.</p>
<p>Field Notes of the exterior boundaries of T. 2, N. R. 30 E. Survey made by David P. Thompson, under Contract No. 83, dated July 22, 1859.</p>	
<p>Beginning at the post, the established corner to Tps. 1 &amp; 2, North of Ranges 29 &amp; 30 East, I ran North between Secs. 31 &amp; 36.</p> <p style="text-align: right;">Variation 18° 30 East.</p>	
40.00	<p>Set post for 1/4 Sec. corner in mound of earth with charred stake &amp;c., as per instructions.</p>
80.00	<p>Set post for corner to Secs. 30, 31, 25 &amp; 36 in mound of earth &amp;c., as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, good, 2nd rate.</p> <p>August 18th, 1859.</p>
<p>North between Secs. 25 &amp; 30.</p> <p style="text-align: right;">Variation 19° 30' East.</p>	
40.00	<p>Set post for 1/4 Sec. corner in mound of earth &amp;c., as per instructions.</p>
80.00	<p>Set post for corner to Secs. 24, 25, 19 &amp; 30 in mound of</p>