

chains

a birch 8 in. diameter bears S. 7° W. 18 links dist.  
 63.83 Umatilla River 100 links wide runs N.W.  
 72.00 Leave timber, course bears N.W. & S.E.  
 86.20 The corner to Townships 2 & 3, North of Ranges 28 & 30 E.  
 Land, level.  
 Soil, 1st rate.  
 Timber: Cottonwood and birch.  
 August 19th, 1859.

General Description

The quality of land in this township is generally good,  
 2nd rate prairie.  
 There is a considerable amount of timber on the Umatilla  
 River, running through Sec. 6.  
 The Umatilla River is about 100 links wide, very swift  
 current; clear, cold water.  
 This township will admit of large settlement, and should  
 be subdivided.

Field Notes of the Survey of  
 Subdivisions of T. 2, N.R. 30 E.  
 Survey made by David P. Thompson  
 Under Contract No. 83.  
 Dated July 22, 1859.

North between Secs. 35 & 36.

40.00 Set post for  $\frac{1}{4}$  Sec. corner in mound of earth &c., as per  
 instructions.  
 80.00 Set post for corner to Secs. 25, 26, 35 & 36 in mound of  
 earth &c., as per instructions.  
 Land, gently rolling.  
 Soil, 2nd rate.

East on a random line between Secs. 25 & 36.

40.00 Set post for temporary  $\frac{1}{4}$  Sec. corner.  
 79.76 Intersect East boundary 35 links South of Sec. corner.  
 S. 89° 45' W. on true line between Secs. 25 & 36.