

Subdivisions T. 2 N. R. 30 E.

Chains	
40.00	Set post for temp. 1/4 Sec. corner.
80.20	Intersect N & S line 18 links North of Sec. corner. S. 89° 52' W. on true line between Secs. 27 & 34.
40.10	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
76.70	Dry Hollow bears N. 20° W.
80.20	The corner to Secs. 27, 28, 33 & 34. Land, gently rolling. Soil, 2nd rate.
<hr/>	
North between Secs. 27 & 28.	
Variation 20° 15' East.	
7.25	Dry Creek bears N. 20° W.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 21, 22, 27 & 28 in mound of earth &c., as per instructions. Land, gently rolling. Soil, 2nd rate.
<hr/>	
East on a random line between Sections 22 & 27.	
40.00	Set post for temp. 1/4 Sec. corner.
80.30	Intersect N & S line 19 links North of Sec. corner. N. 89° 52' W. on true line between Secs. 22 & 27.
40.15	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.30	The corner to Secs. 21, 22, 27 & 28. Land, gently rolling. Soil, 1st rate.
<hr/>	
North between Secs. 21 & 22.	
Variation 20° 15' East.	
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 15, 16, 21, & 22 in mound of