

Subdivisions T. 2 N. R. 30 E.

Chains

North between Secs. 9 & 10.

Variation 20° 30' East.

40.00 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.

46.50 Enter bottom, bears E & W.

70.00 River bears S.W., 160 links wide.

80.00 Set post for corner to Secs. 3, 4, 9 & 10, in mound of stone.

Land, gently rolling.

South 1/2, 2nd rate.

North 1/2, 1st rate.

Timber on River, balm.

East on random line between Secs. 3 & 10.

40.00 Set post for temp. 1/4 Sec. corner.

80.00 Intersect N & S line at corner.

West on true line between Secs. 3 & 10.

30.50 Umatilla River 150 links wide runs S. 70° W.

33.00 Leave river, bears S. 45° W.

40.00 Set post for 1/4 Sec. corner from which
a balm 18 in. diam bears S. 13° W. 20 links dist.

" " 16 " " " N. 78° E. 44 " "

40.50 Deep slough bears S. 75° W. 75 links wide.

57.30 Ascend hill, bears N. 70° E & S 45° W.

62.00 Summit of same bears N. 70° E. & S. 45° W.

80.00 The corner to Secs. 3, 4, 9 & 10.

Land, mostly level.

Soil, 1st rate.

Timber on River, balm.

North on a random line between Secs. 3 & 4.

Variations 18° East.

40.00 Set post for temp. 1/4 Sec. corner.

79.54 Intersect North boundary 50 links West of Sec. corner.

S. 0° 21' W. on true line between Secs. 3 & 4.