

Field Notes of the Survey of the Exterior  
 Boundaries of Township 2 N., R. 31 East,  
 Survey by Josiah A. Burnett, under Contract  
 No. 92, dated September 12th, 1860.

Chains	
	<p>Beginning at the established corner to Townships 1 &amp; 2 North Ranges 31 &amp; 32 East at a post in mound.</p> <p>West on random line along the North boundary of Secs. 1, 2, 3, 4, 5 &amp; 6.</p> <p style="text-align: right;">Variation 21° 15' E.</p> <p>I set temporary half mile and mile posts at every 40.00 chains, 80 chains and at 6 miles, 9 chains and 25 links to a point 3 chains and 84 links South of the corner to Townships 1 &amp; 2 North Ranges 30 &amp; 31 East. Therefore, the correction will be 64 links South per mile.</p> <p>I find the corner post standing with mound and trench.</p> <p>From the corner to Townships 1 &amp; 2 North Ranges 30 &amp; 31 East, I run S. 89° 33' E. on true line along the North boundary of Sec. 6.</p>
49.25	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound, with trench, as per instructions.
64.00	Top of ridge bears N. & S.
89.25	Set post for corner to Secs. 5, 6, 31 and 32. Drove charred stake and raised mound with trench, as per instructions.
	Land, 2nd rate soil.
	<hr/> <p>S. 89° 33' E. on a true line along the North boundary of Sec. 5.</p> <p style="text-align: right;">Variation 17° 00' E.</p>
40.00	Set post for $\frac{1}{4}$ Sec. corner. Drove charred stake and raised mound with trench, as per instructions.
80.00	Set post for corner to Secs. 4, 5, 32 & 33. Drove charred stake and raised mound with trench, as per instructions.
	Land, rolling.
	Soil, 2nd rate.