

S. Bdry, T. 2 N., R. 31 E.

Chains	
	<p>S. 89° 33' E. on a true line along the North boundary of Sec. 4.</p> <p style="text-align: right;">Variation 18° 30' East.</p>
4.00	To bed of a dry ravine, course N.E.
40.00	Set a post for $\frac{1}{4}$ Sec. corner. Drove a charred stake and raised mound with trench, as per instructions.
75.50	Head of a dry ravine, course N.E.
80.00	Set post for corner to Secs. 3, 4, 33 & 34. Drove charred stake and raised mound with trench, as per instructions.
	<p>Land, broken hills.</p> <p>Soil, poor, stony.</p>
	<p>S. 89° 33' E. on a true line along the North boundary of Sec. 3.</p> <p style="text-align: right;">Variation 20° 00' East.</p>
40.00	Set post for $\frac{1}{4}$ Sec. corner. Drove charred stake and raised mound with trench, as per instructions.
80.00	Set a post for corner to Secs. 2, 3, 34 and 35. Drove charred stake and raised mound with trench, as per instructions.
	<p>Land, grass hills.</p> <p>Soil, 2nd rate; sandy.</p>
	<p>S. 89° 33' E. on true line along the North boundary of Sec. 2</p> <p style="text-align: right;">Variation 20° 20' East</p>
33.00	To a dry ravine, course N.E.
40.00	Set a post for $\frac{1}{4}$ Sec. corner. Drove charred stake and raised mound with trench, as per instructions.
80.00	Set a post for corner to Secs. 1, 2, 35 and 36. Drove charred stake and raised mound with trench, as per instructions.
	<p>Land, rolling grass hills.</p> <p>Soil, 2nd rate.</p>