

E. Bdry. T. 2 N., R. 31 E.

Chains

75.50 To the left bank of Umatilla River, a shallow, rapid stream, 100 links wide, runs West.

80.00 Set a post for corner to Secs. 7, 12, 13 & 18, from which a Balm Gilliad, 8 in. dia. bears N. 5° E. 16 links

" " " 12 " " " N.31° W. 5 links dist

" " " 12 " " " S.50° E.10 " "

" " " 10 " " " S.53° W.14 " "

Land, 16.00 chs. South end and 13.00 chs. North end, level; soil, light, sandy; the center, rolling grass hills; soil, 2nd rate.

Timber on the Umatilla River bottom: Balm, Birch and Willow.

North on the East boundary of Sec. 12.

Variation 17° 30' E.

00.50 Leave river bottom and enter rolling hills, bearing E&W.

12.50 Mr. Daniel's house bears East.

40.00 Set a post for  $\frac{1}{4}$  Sec. cor. and raised mound with trench, as per instructions.

70.70 Road from Dalles to Umatilla Agency N.70° E., S.70° W.

80.00 Set post for corner to Secs. 6, 7, 1 & 12, drove charred stake and raised mound with trench, as per instructions.

Land, rolling grass hills.

Soil, 2nd rate.

North on the East boundary of Sec. 1.

Variation 20°00' E.

40.00 Set a post for  $\frac{1}{4}$  Sec. corner, drove charred stake and raised mound with trench, as per instructions.

80.00 To a point for corner to Townships 2 & 3 North, Ranges 31 & 32 East, drove charred stake and raised mound with trench, as per instructions.

Land, rolling grass hills.

Soil, 2nd rate.

Oct. 19th, 1860.