

N. Bdry. T. 2 N., R. 31 E.

Chains	
	<p>West on a random line along the North boundaries of Secs. 1, 2, 3, 4, 5 & 6.</p> <p style="text-align: right;">Variation 19°15' E.</p> <p>I set temporary half mile and mile posts at every 40 and 80 chains and at 6 miles, 2 chains and 60 links to a point 600 links South of the corner to Townships 2 & 3 North Ranges 30 & 31 East. Therefore, the correction will be 100 links South per mile.</p> <p>I find the post and mound standing, with trench.</p> <p>Note: In closing this line on the meridian, I find it falls short of the measurement of the North boundary of T. 1 N. R. 31 E., 4.65 chains. I, therefore, re-measure the North boundary of T. 2 N. R. 31 E; also re-trace East boundary of same and find it correct. The error is in the course of the guide meridian.</p> <p>From the corner to Townships 2 & 3 North Range 30 & 31 E., I run S. 89° 17' E. on a true line along the North boundary of Sec. 6.</p>
44.60	Set a post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
84.60	Set post for corner to Secs. 5, 6, 31 and 32, drove a charred stake and raised mound with trench, as per instructions.
	Land, rolling table lands.
	Soil, 2nd rate.
	<hr/> <p>S. 89° 17' E. on true line along the North boundary of Sec. 5.</p> <p style="text-align: right;">Variation 19°20' E.</p>
40.00	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench as per instructions.
80.00	Set a post for corner to Secs. 4, 5, 32 & 33. Drove a charred stake and raised mound with trench, as per instructions.
	Land, gently rolling prairie.