

Subdivisions, T. 2 N., R. 31 E.

| Chains | |
|---|---|
| 78.00 | Left bank of the Umatilla River, 150 lks. wide, rapid current, low banks, course West. |
| 80.00 | Set post for corner to Secs. 11, 12, 13 and 14, from which A Cottonwood, 8 in. dia. bears N.30° E., 15 lks. dist. A Cottonwood 4 " " " N.10° W., 12 " " " No other tree convenient, I, therefore, dug trench, as per instructions. Land, river bottom, 1st rate; the balance 2nd rate soil. |
| East on random line between Secs. 12 and 13. Variation 21° 30' E. | |
| 40.00 | Set temporary $\frac{1}{4}$ Sec. corner. |
| 79.50 | Intersect East boundary of Township, 78 links North of the corner to Secs. 12 and 13, from which corner I run N. 89° 27' W. on a true line between Secs. 12 and 13. |
| 39.75 | Set post for $\frac{1}{4}$ Sec. cor., drove charred stake and raised mound with trench, as per instructions. |
| 79.50 | The corner to Secs. 11, 12, 13 and 14. Land, rolling. Soil, 2nd rate. |
| North between Secs. 11 & 12. | |
| 2.00 | Leave River bottom, bearing E & S.W. |
| 12.00 | Foot of hill, bearing E. & S.W. |
| 40.00 | Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised stone mound, with trench, as per instructions. |
| 80.00 | Set post for corner to Secs. 1, 2, 11 and 12. Drove charred stake and raised stone mound with trench, as per instructions. Land, rolling grass hills. Soil, 2nd rate. |
| October 21st, 1860. | |
| East on random line between Secs. 1 and 12. Variation 20° 00' East | |