

Subdivisions, T. 2 N., R. 31 E.

Chains	
	North between Secs. 22 & 23.
40.00	Set a post for $\frac{1}{4}$ Sec. corner. Drove charred stake and raised mound, as per instructions.
80.00	Set a post for corner to Secs. 14, 15, 22 and 23, drove charred stake and raised mound with trench, as per instructions.
	Land, rolling, grass hills.
	Soil, 2nd rate.
	East on a random line between Secs. 14 and 23.
	Variation $21^{\circ} 30'$ E.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.80	Intersected N & S line 50 links North of the corner to Secs. 13, 14, 23 and 24, from which I run N. $89^{\circ} 39'$ W. on a true line between Secs. 14 and 23.
21.00	To a deep, rocky ravine, runs N.W.
39.90	Set a post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions..
79.80	The corner to Secs. 15, 14, 23 and 22.
	Land, West half good, 2d rate soil. East half, broken.
	North between Secs. 14 and 15.
6.25	To the top of a bluff, 300 foot high, on the South and left bank of the Umatilla River, bearing E & W., I offset West, 12.00 chs. dist., thence N. on offset line 14.75 chains; offset East 12.00 chs. dist. and regained line at the edge of river.
21.00	Bottom, bearing E & W.
25.00	Left bank of Umatilla River, 200 links wide, shallow, rapid current, runs West.
27.00	Enter Mr. Cornak's field, bearing E & W.
38.00	Leave field, bearing E & W.
39.00	Leave river bottom and enter uplands, bearing E & W.
40.00	Set a post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.