

Subdivisions, T. 2 N., R. 31 E.

Chains	
	East on random line between Secs. 2 and 11. Variation 21° 30' E.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.00	Intersect N & S line, 88 lks. North of the corner to Secs. 1,2,11 and 12, from which corner I run N. 89° 23' W. on a true line between Secs. 2 and 11.
40.00	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and rais- ed mound with trench, as per instructions.
80.00	The corner to Secs. 2, 3, 10 and 11. Land, rolling. Soil, 2nd & 3rd rate.
	<hr/> North on a random line between Secs. 2 and 3.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.60	Intersect the North boundary of Township, 50 links East of the corner to Secs. 2 and 3, from which corner, I run
17.00	S. 22' E. on a true line between Secs. 2 and 3. To Road from Walla Walla to Dalles, bearing E & W.
40.60	Set a post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
80.60	The corner to Secs. 2, 3, 10 & 11. Land, level. Soil, 2nd rate.
	Oct. 22d, 1860.
	<hr/> North between Secs. 33 and 34.
40.00	Set a post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound, as per instructions.
43.75	To a dry ravine, course N.E.
80.00	Set a post for corner to Secs. 27 & 28, 34 and 35. Drove charred stake and raised mound with trench, as per instructions. Land, stony, grass hills. Soil, poor.