

Subdivisions, T. 3. N., R. 31 E.

Chains	
	East on random line between Secs. 27 and 34. Variation 20° 00' East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.60	Intersected N & S line, 25 links South of the corner to Secs. 26, 27, 34 & 35, from which corner I run S. 89° 49' West on a true line between Secs. 27 and 34.
40.30	Set a post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound, as per instructions.
80.60	The corner to Secs. 27, 28, 33 and 34. Land, 2nd rate soil.
<hr/>	
	North between Secs. 27 & 28.
40.00	Set a post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
80.00	Set post for corner to Secs. 21, 22, 27 & 28, drove charred stake and raised mound with trench, as per instructions. Land, broken and stony.
<hr/>	
	East on a random line between Secs. 22 and 27. Variation 20° 15' E.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.40	Intersected N & S line 22 links South of the corner to Secs. 22, 23, 26 & 27, from which corner I run, S. 89° 57' W. on a true line between Secs. 22 and 27.
40.20	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and rais- ed stone mound, as per instructions.
61.90	To a dry ravine, course North.
80.40	The corner to Secs. 21, 22, 27 & 28. Land, rolling. Soil, 2nd rate.
<hr/>	
	North between Secs. 21 and 22.
40.00	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and rais- ed mound with trench, as per instructions.