

Subdivisions, T.2 N., R. 31 E.

Chains	
	North on a random line between Secs. 3 and 4.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
82.15	Intersected North boundary of Township 96 links East of the corner to Secs. 3 and 4, from which I run S.0°41' E. on true line between Secs. 3 and 4.
19.15	Road from Dalles to Walla Walla.
37.15	Top of table lands, course E & W.
42.15	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
82.15	The corner to Secs. 3, 4, 9 & 10. Land, North $\frac{1}{2}$ level; soil 2d rate. South $\frac{1}{2}$, broken and stony.
	North between Secs. 32 and 33.
40.00	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
80.00	Set a post for corner to Secs. 28, 29, 32 and 33. Drove charred stake and raised mound as per instructions. Land, rolling, poor stony hills.
	East on a random line between Secs. 28 and 33. Variation 21° 30' E
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.30	Intersected N & S line 86 links North of the corner to Secs. 27, 28, 33 and 34, from which corner I run N. 89° 23' W. on a true line between Secs. 28 and 33.
40.15	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
80.30	The corner to Secs. 28, 29, 32 & 33. Land, poor, stony grass hills.
	North between Secs. 28 & 29.
40.00	Set post for $\frac{1}{4}$ Sec. corner and raised stone mound, as per instructions.
75.50	To a deep, dry ravine, course N.E.
80.90	Set post for corner to Secs. 20, 21, 28 & 29, drove charred