

Subdivisions, T.2 N., R. 31 E.

Chains	
	raised mound with trench, as per instructions.
79.87	The corner to Secs. 17, 18, 19 & 20. Land, broken. Soil, 3rd rate.
<hr/>	
	West on a random line between Secs. 18 & 19.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
89.80	Intersected West boundary of Township 206 links South of the corner to Secs. 18 & 19, from which corner I run S.88° 32' E. on a true line between Secs. 18 & 19.
49.80	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
60.00	To a deep ravine, course North.
89.80	The corner to Secs. 17, 18, 19 & 20. Land, rolling. Soil, 2d & 3rd rate.
<hr/>	
	North between Secs. 17 & 18.
40.00	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
70.00	Leave uplands and entered bottom, bearing E & W.
74.50	Left bank of Umatilla River, 75 links wide, runs West.
78.00	Leave timbered bottom and enter uplands, bearing E & W.
80.00	Set post for corner to Secs. 7, 8, 17 & 18. Drove charred stake and raised mound with trench, as per instructions. Land (except river bottom) broken; river bottom, 1st and 2nd rate soil.
	Oct. 25th, 1860.
<hr/>	
	East on a random line between Secs. 8 and 17. Variation 22° 30' East
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.72	Intersected N & S line 70 links North of the corner to Secs. 8, 9, 16 & 17, from which corner I run N. 89° 30' West on true line between Secs. 8 & 17.