

Subdivisions, T. 2 N., R. 31 E.

Chains	
	<p>East on random line between Secs. 5 & 8.</p> <p style="text-align: right;">Variation 21°00' E.</p>
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.80	<p>Intersected N & S line 50 links, North of corner to Secs. 4, 5, 8 and 9 from which corner I run</p> <p>N.89° 39' W. on a true line between Secs. 5 & 8.</p>
39.90	Set post for $\frac{1}{4}$ Sec. corner; drove charred stake and raised mound with trench, as per instructions.
79.80	<p>The corner to Secs. 5, 6, 7 & 8.</p> <p>Land, rolling.</p> <p>Soil, 2nd rate.</p>
	<p>West on random line between Secs. 6 & 7.</p>
40.00	Set a post for temporary $\frac{1}{4}$ Sec. corner.
85.92	<p>Intersected West boundary of Township 228 links South of the corner to Secs. 6 & 7; from which corner I run</p> <p>S.88°23' E. on a true line between Sects. 6 & 7.</p>
45.92	Set post for $\frac{1}{4}$ Sec. corner and raised stone mound, as per instructions.
85.92	<p>The corner to Secs. 5, 6, 7, and 8.</p> <p>Land, broken and stony.</p> <p>Note: Dist. 85.92 chains, caused by error in Meridian.</p>
	<p>North on a random line between Secs. 5 & 6.</p>
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
83.87	<p>Intersected North boundary of the Township 224 links East of the corner to Secs. 5 & 6, from which I run</p> <p>S.1° 36' E. on a true line between Secs. 5 & 6.</p>
43.87	Set post for $\frac{1}{4}$ Sec. corner; drove charred stake and raised mound with trench, as per instructions.
83.87	<p>The corner to Secs. 5, 6, 7 & 8.</p> <p>Land, level.</p> <p>Soil, 2nd rate.</p>