

Exteriors, T. 2 N., R. 32 E.

Chains

and falling to be 100 links North of Township corner.
The correction will, therefore, be 16-2/3 links South
per mile.

North 39° 53' E. on North boundary of Sec. 6.

Variation 20° East.

46.50 Set stone 20 x 10 x 4 in. for $\frac{1}{4}$ Sec. corner.

86.50 Set post for corner to Secs. 5, 6, 31 and 32 in mound of
earth with charred stake, pits, trench &c., as per
instructions.

Land, hilly, sloping South.

Soil, good 2nd rate.

September 11th, 1864.

N. 89°53' E. on North boundary of Sec. 5.

Variation 20° East.

P.50 Emigrant Road bears N.W. & S.E.

40.00 Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred
stake, pits, trench &c., as per instructions.

80.00 Set stone 18 x 10 x 8 in. for corner to secs. 4, 5, 32
and 33 in ravine that bears N & S.

Land, rolling, sloping south.

Soil, 2nd rate.

North 89° 53' East on North boundary of Sec. 4.

Variation 20° East.

40.00 Set post for $\frac{1}{4}$ Sec. corner.

67.00 Ravine bears N & S.

80.00 Set post for corner to Secs. 3, 4, 33 & 34 in mound of
earth, with charred stake, pits, trench &c., as per
instructions.

Land, rolling, sloping South.

Soil, 2nd rate.
