

Exteriors. T. 2. N., R. 32 E.

Chains

N. 89° 53' East on North boundary of Sec. 3.

Variation 20° East.

40.00 Set post for  $\frac{1}{4}$  Sec. corner in mound of earth with charred stake, pits, trench &c., as per instructions.

55.30 Road from Umatilla to Walla Walla bears N.E. & S.W.

80.00 Set post for corner to Secs. 2, 3, 34 and 35 in mound of earth with charred stake, pit and trench &c., as per instructions.

Land, rolling.

Soil, 2nd rate.

N. 89° 53' East on North boundary of Sec. 2.

Variation 20° East.

40.00 Set  $\frac{1}{4}$  Sec. corner in mound of earth with charred stake, pits, trench &c., as per instructions.

80.00 Set post for corner to Secs. 1, 2, 35 & 36 in mound of earth with charred stake, pits, trench &c., as per instructions.

Land, rolling, sloping South.

Soil, good 2nd rate.

N. 89° 53' E. on North boundary of Sec. 1.

Variation 20° East.

40.00 Set post for  $\frac{1}{4}$  Sec. corner in mound of earth with charred stake, pits, trench &c., as per instructions.

75.00 Ravine bears NE & SW.

80.00 The established corner to Townships 2 & 3 North Ranges 32 & 33 East.

Land, rolling.

Soil, 2nd rate.

September 13th, 1864.

General Description

The land in this Township is generally rolling, is well watered and a large amount of timber on the Umatilla