

Subdivisions, T. 2 N., R. 32 E.

Chains	
	<p>Land, gently rolling. Soil, 1st rate.</p> <hr/> <p>East on a random line between Secs. 24 & 25.</p>
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.
79.50	Intersect East boundary 35 links South of corner to Secs. 24 & 25, from which I run S. $89^{\circ} 45'$ W. on a true line between Secs. 24 & 25.
39.75	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.
79.50	The corner to Secs. 23, 24, 25 & 26. Land, rolling. Soil, 2nd rate.
	<hr/> <p>North between Secs. 23 & 24. Variation $20\frac{1}{2}^{\circ}$ East</p>
40.00	Set stone 24 x 10 x 4 for $\frac{1}{4}$ Sec. corner.
42.20	Ravine bears N.W.
30.00	Set stone 18 x 8 x 6 for corner to Secs. 13, 14, 23 & 24. Land, rolling. Soil, 1st rate.
	<hr/> <p>East on a random line between Secs. 13 & 24.</p>
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.
79.41	Intersect East boundary 43 links South of corner to Secs. 13 & 24, from which I run S. $89^{\circ} 42'$ W. on a true line between Secs. 13 & 24.
39.70	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.
79.41	The corner to Secs. 13, 14, 23 & 24. Land, gently rolling. Soil, 2nd rate.