

Subdivisions, T. 2 N., R.32 E.

Chains		
	North between Secs. 13 & 14.	
		Variation $20\frac{1}{4}^{\circ}$ East.
	Descend hill.	
37.50	Foot of hill	-150
40.00	Set stone 18 x 12 x 6 for $\frac{1}{4}$ Sec. corner.	
41.20	Dry bed of creek bears N.W.	
45.00	Ascend hill.	
80.00	Set post for corner to secs. 11, 12, 13 & 14 in mound of earth with charred stake, pits &c., as per instructions	+150
	Land, rolling.	
	Soil, 2nd rate.	
<hr/>		
	East on a random line between Secs. 12 & 13.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.	
79.60	Intersect East boundary 35 links North of corner to Secs. 12 & 13, from which I run	
	N. $89^{\circ} 45'$ W. on a true line between Secs. 12 & 13.	
39.80	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.	
79.60	The corner to Secs. 11, 12, 13 & 14.	
	Land, gently rolling.	
	Soil, 1st rate.	
<hr/>		
	North between Secs. 11 & 12.	
		Variation $20\frac{1}{4}^{\circ}$ East
28.50	Road bears E & W.	
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth, with charred stake, pits &c., as per instructions.	
77.00	Road bears E & W.	
80.00	Set stone 30 x 10 x 5 for corner to Secs. 1, 2, 11 & 12.	
	Land, rolling.	
	Soil, 2nd rate.	
<hr/>		
	East on a random line between Secs. 1 & 12.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.	