

Subdivisions, T. 2 N., R. 32 E.

| Chains | |
|--------|---|
| | <p>North between Secs. 22 & 23.</p> <p style="text-align: right;">Variation 19° East.</p> |
| 40.00 | Set stone 18 x 10 x 10 for $\frac{1}{4}$ Sec. corner. |
| 64.00 | Ravine bears N.W. |
| 80.00 | Set post for corner to Secs. 14, 15, 22 & 23 in mound of earth with charred stake, pits &c., as per instructions. |
| | Land, rolling. |
| | Soil, 2nd rate. |
| <hr/> | |
| | East on a random line between Secs. 14 & 23. |
| 40.00 | Set post for temporary $\frac{1}{4}$ Sec. corner. |
| 79.90 | Intersect N & S line at corner to Secs. 13, 14, 23 & 24, from which I run |
| | West on a true line between Secs. 14 & 23. |
| 39.95 | Set stone 18 x 14 x 6 for $\frac{1}{4}$ Sec. corner. |
| 40.50 | Ravine bears N.W. |
| 79.90 | The corner to Secs. 14, 15, 22 & 23. |
| | Land, gently rolling. |
| | Soil, 2nd rate. |
| <hr/> | |
| | North between Secs. 14 & 15. |
| | Variation, 22° East |
| 40.00 | Set post for $\frac{1}{4}$ Sec. corner. |
| 45.50 | Dry bed of creek, bears N.W. |
| 53.00 | Ascend hill. |
| 80.00 | Set stone 18 x 12 x 12 for corner to secs. 10, 11, 14 & 15. |
| | Land, rolling. |
| | Soil, good 2nd rate. |
| <hr/> | |
| | East on a random line between Secs. 11 & 14. |
| 40.00 | Set post for temporary $\frac{1}{4}$ Sec. corner. |
| 80.35 | Intersect N & S line at corner to Secs. 11, 12, 13 & 14, from which corner I run |
| | West on a true line between Secs. 11 & 14. |
| 40.17 | Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred |

+200