

11
Subdivisions, T. 2 N., R. 32 E.

Chains	
	stake, pits &c., as per instructions.
80.35	The corner to Secs. 10, 11, 14 & 15. Land, rolling. Soil, 2nd rate.
<hr/>	
	North between Secs. 10 & 11. Variation $20\frac{1}{2}^{\circ}$ East
9.25	Road bears E & W.
35.00	Foot of hill.
40.00	Set stone 20 x 8 x 6 for $\frac{1}{4}$ Sec. corner.
58.75	Road, bears East and West.
64.25	Enter field, bears E & W.
70.00	House bears East 10 links dist.
80.00	Set stone 18 x 8 x 8 for corner to Secs. 2, 3, 10 and 11. Land, level. Soil, 1st rate.
<hr/>	
	East on a random line between Secs. 2 & 11.
40.00	Set post for temp. $\frac{1}{4}$ Sec. corner.
80.30	Intersect N & S line at post for corner to Secs. 1, 2, 11 and 12, from which I run West on a true line between Secs. 2 & 11.
35.25	Field bears N.E. & S.W.
40.15	Set post for $\frac{1}{4}$ Sec. corner in mound of earth, with charred stake, pits &c., as per instructions.
44.18	Leave field N & S.
46.50	A. Miller's house bears S. 65° W. 300 links dist.
70.00	Enter field, bears N & S.
80.30	The corner to Secs. 2, 3, 10 & 11. Land, level river bottom. Soil, 1st rate. Scattering Cottonwood timber.
<hr/>	
	North on a random line between Secs. 2 & 3. Variation 19° East.