

Subdivisions, T. 2 N., R. 32 E.

Chains		
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.	
79.89	Intersect North boundary at corner to secs. 2 & 3, from which I run South on a true line between Secs. 2 & 3. Descend hill.	
39.89	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.	
76.00	Foot of hill, Umatilla River, 100 links wide, runs S.W.	-200
79.89	The corner to secs. 2, 3, 10 & 11. Land, hilly. Soil, 2nd rate.	
		Nov. 1st, 1864.
<hr/>		
	North between Secs. 33 & 34 Descend hill.	
40.00	Set post for $\frac{1}{4}$ Sec. cor. in mound earth with charred stake, pits, &c., as per instructions.	
59.00	Foot of hill.	-200
62.00	Dry bed of creek, bears N. 5° W.	
80.00	Set post for corner to secs. 33, 34, 27 & 28 in mound of gravel, with pits, charred stake &c., as per instruc- tions. Land, rolling. Soil, 2nd rate.	
<hr/>		
	East on a random line between Secs. 27 & 34.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.	
79.80	Intersect N & S line 25 links North of corner to secs. 26, 27, 34 & 35, from which corner I run N. 89° 49' W. on a true line between secs. 27 & 34. Descend hill.	
39.90	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions. Foot of hill.	
79.80	The corner to Secs. 33, 34, 27 & 28. Land, gently rolling. Soil, 1st rate.	