

Subdivisions, T. 2 N., R. 32 E.

Chains		
	North between Secs. 27 & 28.	
	Variation 20° East..	
39.00	Dry bed of creek, course Northeast.	
40.00	Set post for $\frac{1}{4}$ Sec. corner, from which	
	a Balm 12 in. diam. bears S.24° E.100 links dist.	
	" " 5 " " " N.70° W. 80 " "	
49.00	Dry bed of creek, course N.W.	
50.00	Ascend hill.	
80.00	Set stone 18 x 10 x 5 for corner to secs. 21, 22, 27 & 28.	+150
	Land, gently rolling.	
	Soil, 2nd rate.	
	Some Cottonwood timber.	
<hr/>		
	East on a random line between Secs. 22 & 27.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.	
79.80	Intersect N & S line at corner to Secs. 22, 23, 26 & 27,	
	from which I run	
	West on a true line between Secs. 22 & 27.	
17.00	Prairie bears North.	
39.90	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred	
	stake, pits &c., as per instructions.	
79.80	The corner to Secs. 21, 22, 27 & 28.	
	Land, rolling.	
	Soil, 2nd rate.	
<hr/>		
	North between Secs. 21 & 22.	
	Variation 19 $\frac{1}{4}$ ° East	
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth, with charred	
	stake, pits &c., as per instructions.	
80.00	Set post for corner to Secs. 15, 16, 21 & 22 in mound of	
	earth, with charred stake, pits &c., as per instructions.	
	Land, rolling.	
	Soil, 2nd rate.	
<hr/>		