

Subdivisions, T. 2 N., R. 32 E.

Chains

33.30 Enter field, bears E & W.
 40.00 Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred
 stake, pits &c., as per instructions.
 House bears S. 55° W., 700 links distant.
 51.75 Leave field, bears E & W.
 65.20 Umatilla River, 100 links wide, runs West.
 68.00 Ascend hill.
 73.50 Old Emigrant Road bears E & W.
 80.00 Set post for corner to secs. 3, 4, 9 & 10. † 50
 Land, level.
 Soil, 1st rate.

East on a random line between secs. 3 & 10.

40.00 Set post for temporary $\frac{1}{4}$ Sec. corner.
 79.80 Intersect N & S line 50 links North of corner to secs.
 2, 3, 10 and 11, from which I run
 N. 89° 39' W. on a true line between Secs. 3 & 10.
 3.40 Umatilla River, 100 links wide, runs S.W.
 14.50 Store bears S. 20° W., 20 chains distant.
 39.90 Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charr-
 ed stake, pits &c., as per instructions.
 79.80 The corner to secs. 3, 4, 9 & 10.
 Land, gently rolling.
 Soil, 2nd rate.

North on a random line between Secs. 3 & 4.

Variation $18\frac{1}{2}^{\circ}$ East

40.00 Set post for temporary $\frac{1}{4}$ Sec. corner.
 80.20 Intersect North boundary 60 links East of corner to
 Secs. 3 & 4, from which I run
 S. 0° 26' E. on a true line between Secs. 3 & 4.
 Descend hill.
 40.20 Set stone 14 x 10 x 10 for $\frac{1}{4}$ Sec. corner.
 51.90 Walla Walla and Umatilla Road bears N.E. and S.W.
 80.20 The corner to Secs. 3, 4, 9 & 10. † 300
 Land, hilly.
 Soil, 2nd rate.