

Subdivisions T. 2 N., R. 32 E.

Chains		
	Ascend hill.	
47.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.	
87.00	The corner to Secs. 17, 18, 19 & 20.	+300
	Land, hilly.	
	Soil, good 2nd rate.	
<hr/>		
	North between Secs. 17 & 18.	
	Variation 21° E.	
20.00	Descend hill.	
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.	
75.50	Ravine bears N.E.	
80.00	Set stone 24 x 14 x 5 for corner to Secs. 7, 8, 17 & 18.	-350
	Land, rolling.	
	Soil, 2nd rate.	
<hr/>		
	East on a random line between Secs. 8 & 17.	
40.00	Set post for temporary $\frac{1}{4}$ Section corner.	
80.80	Intersect N & S line 35 links North of corner to Secs. 8, 9, 16 & 17 in dry bed of creek, from which I run N. 89°45' W. on a true line between Secs. 8 & 17.	
6.50	Leave brush, bears N & S.	
40.40	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.	
80.80	The corner to Secs. 7, 8, 17 & 18.	
	Land, rolling.	
	Soil, good 2nd rate.	
<hr/>		
	West on a random line between Secs. 7 & 18.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.	
86.70	Intersect West boundary at corner to sections 7 & 18, from which corner I run	
	East on a true line between Secs. 7 & 18.	
11.25	Umatilla River 150 links wide, runs South 80° W.	