

22
Subdivisions, T. 2 N., R. 32 E.

Chains	
46.70	Set post for temporary $\frac{1}{4}$ Sec. corner.
84.50	Ravine bears North.
86.70	The corner to Secs. 7, 8, 17 & 18. Land, rolling. Soil, 2nd rate.
North between Secs. 7 & 8.	
Variation 20° East	
40.00	Set stone 17 x 8 x 5 for $\frac{1}{4}$ Sec. corner from which a Balm 15 in. diam. bears S. 46° W., 40 links dist. Enter timber, bears E & W.
43.00	Umatilla River, 150 links wide, runs W.
47.75	Enter field and leave timber, bears E & W.
51.25	Leave field, bears E & W. Ascend hill. House bears E. 4.00 links distant.
59.20	Old Emigrant Road bears E & W.
80.00	Set post for corner to secs. 5, 6, 7 & 8 in mound of earth with charred stake, pits &c., as per instructions. 1150 Land, rolling. Soil, 2nd rate.
East on a random line between Secs. 5 & 8.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.
80.30	Intersect N & S line at corner to Secs. 4, 5, 8 & 9, from which I run West on a true line between Secs. 5 & 8.
21.20	Judge J. W. Johnson's house bears S. 4 chains distant.
40.15	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.
80.30	The corner to Secs. 5, 6, 7 & 8. Land, rolling. Soil, 2nd rate.
West on a random line between Secs. 6 & 7.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.
87.32	Intersect West boundary 70 links South of corner to Secs.