

Field Notes of the Survey of the  
W. Boundary of Township 2 N.R. 33 E.  
Survey by Zenas F. Moody, under his  
Contract No.145, dated April 23, 1871.  
(E. bdry. of T.2 N.R. 32 E.)

Chains		
	From the Southwest corner of Tp. 2 N. R. 33 East, I run North on random between Ranges 32 & 33 East.	
	I set half mile and mile posts at every 40 & 80 chains and at 6 miles and 50 links to a point 2 chains and 44 links East of the South East corner to Township 3 N. Range 32 East.	
	Thence	
	S. 00° 18' East on West line of Sec. 6.	
	Variation 21° East.	
15.00	Wagon road, course N. E. & S.W.	
15.50	Wild Horse Creek, 10 links, flows S.W.	
40.50	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.	
80.50	Set post and made earth mound for corner to Secs. 6, 7, 1 and 12.	
	Land, rolling.	
	Soil, 1st rate.	
<hr/>		
	S. 00° 18' East on West boundary of Section 7.	
	Variation 21° East.	
13.00	Umatilla River, 2 chains, flows W.N.W., N.W. by S.E.	
25.00	Leave river bottom and enter field.	
36.00	Leave field, fence bears E & W.	
40.00	Set post and made mound of earth for $\frac{1}{2}$ Sec. corner.	+100
60.00	Summit of ridge.	+250
72.00	LaGrande and Pendleton road N.W., S.E.	
80.00	Set post and made earth mound corner to Secs. 7, 18, 12 & 13.	
	Land, rolling.	
	Soil, 1st rate.	
<hr/>		
	S.00°18' East on West boundary of Sec. 18.	
	Variation 21°30'.	
34.00	Tudie Willow, 7 links, flows N.W.	-200
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.	
80.00	Set post and made mound of earth for corner to Secs.	