

Subdivisions, T. 2 N., R. 32 E.

Chains	
40.00	Set temporary $\frac{1}{4}$ S. cor.
80.10	Intersected N & S line at corner. W. on true line.
13.40	Ravine. N & S.
40.05	Set post and made earth mound for $\frac{1}{4}$ Sec. cor.
80.10	To cor. Land, rolling. Soil, 2nd rate.
North bet. Secs. 15 & 16	
40.00	Set post and made earth mound for $\frac{1}{4}$ Sec. cor.
80.00	Set post and made earth mound for cor. to Secs. 15, 16, 9 & 10. Land, rolling. Soil, 2nd rate.
East on random bet. Secs. 10 & 15.	
V. 21° 30' E.	
40.00	Set temporary $\frac{1}{4}$ Sec. cor.
80.00	Intersected N & S line 14 links N. of cor. N. 89° 54' W. on true line.
40.00	Set stone 17 x 14 x 12 for $\frac{1}{4}$ Sec. cor.
46.00	Dry bed, Tudie Willow. N.W.
80.00	To corner. Land, rolling. Soil, 2d rate. Good grass.
North bet. Secs. 9 & 10.	
30.51	To the Boundary of the Umatilla Indian Reservation
West bet. Secs. 21 & 28.	
22.50	Enter Howetome Ck. Bottom.
30.50	Dry bed Howetome Ck. N.
40.00	Set post and made earth mound for $\frac{1}{4}$ S. cor.
42.50	Leave Howetome Ck. bottom.