

Subdivisions T.2 N. R. 32 E.

Chains	
	East on random between Secs. 24 & 25. Var. 21° East.
40.00	Set temp. $\frac{1}{4}$ sec. corner.
79.85	Intersect Township line 70 links North of corner to Secs. 24, 25, 19 & 30. Thence N. 89° 30' W. on true line. Var. 21° 45' East.
16.50	Wagon Road bears N.W.
39.93	Found and reestablished old corner; set stone 9 x 8 x 7 ins., 6 inches in the ground for $\frac{1}{4}$ Sec. corner; marked $\frac{1}{4}$ on N. face; dug pits 18 x 18 x 12 ins. E and W from stone, 5 $\frac{1}{2}$ ft. distant, and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base alongside.
79.85	To corner to Secs. 23, 24, 25 & 26. Land, rolling. Soil, 1st rate. No timber. Poor bunch grass.
	North on random between Secs. 23 & 24. Var. 21° East.
40.00	Set temp. $\frac{1}{4}$ Sec. corner.
79.10	To a point 23 links W. of old corner to Secs. 13, 14, 23 & 24. Reestablished old corner. Set stone 18 x 12 x 6 ins., 12 inches in the ground marked with 3 notches on S. and 1 on E. edges. Dug pits 18 x 18 x 12 ins., in each section, 5 $\frac{1}{2}$ ft. distant, and raised a mound of earth 2 ft. high, 4 $\frac{1}{2}$ ft. base over it. Thence S. 10' W. on true line. Va. 20° East.
37.10	Dry bed of gulch, course W.
39.55	Old $\frac{1}{4}$ Sec. corner. Reset stone 18 x 12 x 6 ins., 12 inches in the ground for $\frac{1}{4}$ Sec. corner; marked $\frac{1}{4}$ on West face. Dug pits 18 x 18 x 12 ins. N. and S. from stone 5 $\frac{1}{2}$ ft. distant and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.