

## Subdivisions, T. 2 N.R. 32 E.

Chains		
79.10	To corner to Secs. 23, 24, 25 & 26. Land, rolling. Soil, good. No timber. Poor grass.	
	East on random between Secs. 13 & 24. Va. 20° East.	
40.00	Set temp. $\frac{1}{4}$ Sec. corner.	
79.62	Intersect Township line 77 links North of corner to Secs. 18, 19, 13 & 21. Thence N. 89° 27' W. on true line. Va. 20° 35' East.	
39.81	Set a stone 12 x 9 x 7 inches, 8 inches in the ground for $\frac{1}{4}$ Sec. corner; marked $\frac{1}{4}$ on N. face. Dug pits 18 x 18 x 12 ins., E. & W. from stone $5\frac{1}{2}$ ft. distant and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
79.62	To corner to Secs. 13, 14, 23 & 24. Land, rolling. Soil, 1st rate. No timber. Poor grass.	
	North on random between Secs. 13 & 14. Va. 20° East.	
40.00	Set temp. $\frac{1}{4}$ Sec. corner.	
79.20	To a point 3 links West of Old Corner to Secs. 11, 12, 13 & 14 reestablished Old Corner with stone 15 x 8 x 4 inches., 10 inches in the ground, marked with 4 notches on S. and 1 notch on E. edges. Dug pits 18 x 18 x 12 inches in each section, $5\frac{1}{2}$ ft. distant and raised a mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it. Thence S. 1' W. on true line. Va. 20° 15' East.	
9.20	Summit of ridge, course S.W.	+50
21.95	Gulch, bears S.W.	-50