

## Subdivisions, T.2 N.R. 32 E.

Chains		
34.20	Road and enter creek bottom W.	
38.00	Tudie Willow Creek, 4 links wide W.	
39.60	To old $\frac{1}{4}$ Sec. corner, which I re-established with a stone 18 x 10 x 8 ins., 12 inches in the ground, marked $\frac{1}{4}$ on W. face; dug pits 18 x 18 x 12 ins., N and S from stone $5\frac{1}{2}$ ft. distant and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
43.70	Leave creek bottom, course E & W.	
69.20	Summit of hill.	+100
79.20	To corner to secs. 13, 14, 23 and 24. Land, generally 1st rate, rocky on South hillsides. No timber; swamp and wire grass in creek bottom; bunch grass on hills.	
East on random between Secs. 12 & 13.		
Var. 20° 15' East.		
40.00	Set temp. $\frac{1}{4}$ Sec. corner.	
79.60	Intersect Township line, 70 links North of corner to Secs. 12, 13, 7 & 18; thence N. 89° 30' W. on true line.	
Var. 20° 20' East.		
39.80	Set stone 10 x 9 x 8 ins., 7 inches in the ground for $\frac{1}{4}$ Sec. corner marked $\frac{1}{4}$ on N face; dug pits 18 x 18 x 12 ins. E & W from stone, $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
51.85	Road bears N and S.	
67.10	Summit of hill.	+40
78.00	Hollow, course S W.	-20
79.60	To corner to Secs. 11, 12, 13 & 14. Land, rolling. Soil, 1st rate. No timber. Bunch and other grass.	
North on true line between Secs. 11 and 12.		
Var. 20° 15' East.		