

## Subdivisions, T. 2 N.R. 32 E.

Chains		
5.15	Gulch, course W.	-50
15.00	Top of hill, bears E & W.	
29.00	Wagon Road bears E & W.	
40.00	Set stone 7 x 8 x 9 ins. 6 inches in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on W. face. Dug pits 18 x 18 x 12 ins., N & S from stone $5\frac{1}{2}$ ft. distant and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
59.85	Intersect line to "Reserve" Addition to the Town of Pendleton. Set a stone 10 x 10 x 12 ins., 8 inches in the ground for U.R. closing corner, marked URCC on S. face; dug pits 18 x 18 x 12 ins. SE and W from stone $5\frac{1}{2}$ ft. distant and raised a mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.	
	Land, rolling.	
	Soil, 1st rate.	
	No timber. Bunch grass.	
<hr/> Beginning at the corner to Secs. 1, 2, 11 and 12, which is a stone 18 x 17 x 6 ins., marked with 5 notches on S and 1 on E edges; thence East on random between secs. 1 and 12.		
		Var. 21° East.
40.00	Set temp. $\frac{1}{4}$ sec. corner.	
80.40	Intersect Township line 58 links North of corner to Secs. 6, 7, 1 & 12; thence N. 89° 35' W. on true line.	
		Var. 20° East.
	Down river bottom through dense brush.	
40.20	Set a stone 18 x 10 x 8 ins., 12 inches in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on N. face from which A Balm 4 ins. diam. bears N. 72° W. 19 lks. distant. marked $\frac{1}{4}$ S. B. T., and A Balm 6 ins. diam., bears S. 70° W. 70 links distant, marked $\frac{1}{4}$ S. B. T. and raised a mound of stone alongside.	