

## Subdivisions, T. 2 N.R. 32 E.

Chains	
53.00	Umatilla River runs N.W. 1.00 ch. wide.
53.25	Pass under Suspension (Wagon Road) bridge.
58.00	O. R. & N. R. R. Course S.E. & N.W.
68.04	" " " " " " " N. E. & S.W.
73.94	To Reserve Addition boundary of Pendleton, set a stone 10 x 8 x 7 ins., 7 inches in the ground for closing corner, marked U.R.C.C. on E. face, dug pits 18 x 18 x 12 ins. N.S.& E. of corner 5½ ft. dist; raised earth mound 2 ft. high, 4½ ft. base alongside.
80.40	To corner to Secs. 1, 2, 11 & 12. Land, mostly in creek bottom. A great deal of gravel. Timber: Cottonwood and dense willow; thorn and other underbrush. 54.00 chains.
North on random between Secs. 1 & 2.	
	Va. 21° East.
40.00	Old ¼ Sec. corner, which is a stone 12 x 8 x 8 ins., 8 inches in the ground, marked with ¼ on W. face in mound of earth; <u>thence South on true line</u> ; descend steep bluff, facing S.
14.00	Enter bottom.
14.60	Set stone 24 x 16 x 8 ins., 16 inches in the ground for meander corner marked M.C., and raised a mound of stone 2 ft. high, 4½ ft. base alongside. Pits impracticable.
17.00	Umatilla River, course S.W., 100 links wide.
25.55	Intersect N.E. Bdry. of "Reserve" Addition to the Town of Pendleton, Oregon. Set stone 18 x 12 x 7 ins., 12 inches in the ground for closing corner to U. R. bdy. Marked U.R.C.C. on North face; dug pits N.E. and W. from stone 5½ ft. dist. and raised a mound of earth 2 ft. high, 4½ ft. base alongside, from which A Balm 6 ins. diam bears S.59°E.20 lks. distant, marked C.C.B.T.
39.00	Mill Race and Creek 50 links wide. Course W.