

Subdivisions, T. 2 N.R. 32 E.

Chains		
	25,26,35 & 36; thence	
	N. 89° 43' W. on true line.	
		Va. 21° East.
6.75	Gulch. Course S.E.	-30
11.00	Summit hill.	+40
15.00	Dry gulch.	-40
19.00	Summit of hill.	+40
30.50	Gulch, course S.	-50
40.12	Set stone 8 x 10 x 12 ins., 8 inches in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on N. face. Dug pits 18 x 18 x 12 ins. E & W. from stone $5\frac{1}{2}$ ft. distant and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. Base over it. Old corner not found.	
48.25	Dry bed of creek, course N.W.	
58.50	Summit of hill.	+30
64.75	Dry Gulch.	-20
70.00	Summit of hill.	+40
78.25	Dry Creek, course N.E.	-20
80.25	To corner to Secs. 26, 27, 34 & 35. Land, rolling. Soil, 1st rate. No timber. Poor bunch grass.	
	North on random between Secs. 26 & 27, retracing <u>old line</u>	
		Va. 21°30' East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.	
80.00	To a point 45 links West of old corner to Secs. 22, 23, 26 & 27, reestablished corner with stone 9 x 8 x 7 ins. 6 inches in the ground, marked with 2 notches on E. and S. edges; dug pits 18 x 18 x 12 ins. in each section, $5\frac{1}{2}$ ft. distant and raised a mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base alongside. Thence S. 19' W. on true line.	
		Va. 20° East.
40.00	Old $\frac{1}{4}$ Sec. corner. Set stone 12 x 10 x 8 ins., 8 inches	