

Subdivisions, T. 2 N.R. 32 E.

Chains		
	South on true line.  Var. 22° 45' East.	
4.00	Gulch, course West.	-20
8.00	Summit of hill.	+30
30.75	Gulch, course S.W.	-20
38.00	Summit of hill.	+30
39.90	Set a stone 20 x 14 x 8 ins., 14 inches in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on W. face; redug pits, 18 x 18 x 12 inches N & S from stone $5\frac{1}{2}$ ft. distant and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.	
79.80	To corner to Secs. 22, 23, 26 & 27.  Land, rolling.  Soil, 1st rate.  No timber. Poor bunch grass.	
<hr/>		
	East on random line between Secs. 14 & 23.  Var. 22° 45' East.	
40.00	Set temp. $\frac{1}{4}$ Sec. corner.	
79.80	Intersect N & S line 70 links N. of corner to Secs. 13, 14, 23 & 24. Thence,  N. 89° 30' W. on true line.  Var. 20° East.	
29.70	Dry gulch, course S.W.	-50
39.90	Set a basalt stone 18 x 16 x 6 inches, 12 inches in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on N. face. Redug pits 18 x 18 x 12 inches, E & W from stone $5\frac{1}{2}$ ft. distant. Raised earth mound $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.	
40.60	Dry gulch, course S.W.	-50
79.80	To corner to Secs. 14, 15, 22 & 23.  Land, rolling.  Soil, 1st rate.  No timber. Poor bunch grass.	