

## Subdivisions, T. 2 N.R. 32 East

Chains		
	North on random between Secs. 14 & 15. Var. 21°45' East.	
40.00	Set temporary $\frac{1}{4}$ Section corner.	
80.00	Intersect N. boundary 20 links E. of old corner to Secs. 10, 11, 14 & 15. Reestablished old corner. Set stone 12 x 10 x 8 inches, 8 inches in the ground, marked 4 notches on S. and 2 on E. edges. Dug pits 18 x 18 x 12 inches in each Section, $5\frac{1}{2}$ ft. distant. Raised earth mound 2 ft. high, $4\frac{1}{2}$ ft. base alongside. Thence S. 9' E. on true line. Var. 21° East.	C
30.00	Enter field and creek bottom.	-70
34.00	Creek, 4 links wide, Course W.	
37.00	Leave creek bottom.	
39.00	Bluff.	
40.00	Set a basalt stone 8 x 8 x 8 inches, 6 inches in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on W. face; dug pits 18 x 18 x 12 inches N & S of corner, $5\frac{1}{2}$ ft. distant. Raised earth mound $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.	C
80.00	To corner to Secs. 14, 15, 22 & 23. Land, rolling, partly cultivated. Soil, 1st rate. No timber; scattering grass.	
	<hr/> East on random between Secs. 11 & 14. Var. 21° East.	
40.00	Set temporary $\frac{1}{4}$ Section corner.	
80.00	Intersect E. boundary 1.40 chains N. of corner to Secs. 11, 12, 13 & 14. Thence N. 89° <del>W.</del> on true line.	C
10.00	Dry ditch. Course North.	
32.00	Summit of ridge.	+100
40.00	Set stone 9 x 8 x 7 ins., 6 inches in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on N. face; dug pits 18 x 18 x	