

Subdivisions, T. 2 N. R. 32 E.

Chains		
40.00	Set temp. $\frac{1}{4}$ sec. cor.	
79.50	Intersect N & S line at Cor. to Secs. 28, 29, 32 & 33, which is a stone 16 x 10 x 10 ins. firmly set in the ground; thence E. on a true line. Var. 21° East.	
51.00	Intersect U. R. bdy. and set stone 10 x 10 x 10 ins., 7 ins. in the ground for U. R. Closing corner. Marked S.28 on N. and S.33 on S. face, U.R.C.C. on E. face. Dug pits E. N & S. 18 x 18 x 12 ins. $5\frac{1}{2}$ ft. dist. and raised a mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.	
61.00	Gulch.	-25
68.50	Summit.	+75
74.50	McKay Creek 10 lks. wide, Course N.	
79.50	To Cor. to Secs. 27, 28, 33 & 34. Land, rolling. Soil, 1st rate. Cottonwood and thorn along creek. Poor grass.	
<hr/> North on random bet. Secs. 27 & 28.		
Var. 20° East.		
40.00	Set temp. $\frac{1}{4}$ Sec. cor.	
80.00	Old Sec. Cor. Reestablished Cor. Set stone 24 x 12 x 10 ins., 16 ins. in the ground for cor. to secs. 21, 22, 27 & 28, marked with 2 notches on S. & 3 on E. edges; dug pits 18 x 18 x 12 ins. in each sec. $5\frac{1}{2}$ ft. dist. and raised a mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it. Thence, S. on true line. Var. 20° East.	
20.00	Top of hill.	+150
30.00	Bluff of rock 20 ft. high, facing W. Descend.	
32.00	Creek.	
40.00	Set stone 10 x 8 x 6 ins. in bed of creek for $\frac{1}{4}$ sec. cor.	