

Subdivisions, T. 2 N.R. 32 E.

Chains	
	<p>Marked $\frac{1}{4}$ on W. face. Set stone 8 x 10 x 12 ins. on W. bank N. 80° W. 60 lks. dist. for witness cor. marked $\frac{1}{2}$ W.C. on W. face, from which</p> <p>a Cottonwood 18 in.diam.bears S.12° E.50 lks. dist. marked $\frac{1}{4}$ S.W.C.B.T., and</p> <p>a Cottonwood 12 ins.diam.bears N.75°W.1.85 chs.dist. marked $\frac{1}{4}$ S.W.C.B.T.</p>
42.00	East bank of McKay Creek, follow bed of creek.
80.00	To cor. to Secs. 27, 28, 33 & 34.
	Land, mostly level bottom.
	Soil, 3rd rate.
	Cottonwood along creek. Poor grass.
<hr/>	
	East on random bet. Secs. 22 & 27.
	Var. 20° East.
40.00	Set temp. $\frac{1}{4}$ Sec. cor.
79.75	Intersect E. bdy. 20 lks. N. of Cor. to Secs. 22,23,26 & 27; thence
	N.89° 57' W. on true line.
16.00	Tudie Willow, 6 lks. wide, course N.W.
17.50	Wagon Road and ascend.
39.87	Set stone 9 x 8 x 7 ins., 6 ins. in the ground in old mound; dug pits 18 x 18 x 12 ins. E. & W. from stone $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
79.75	To Cor. to Secs. 21, 22, 27 & 28.
	Land, smooth and level. Some grass.
	Soil, 2nd rate.
<hr/>	
	North on Random bet. Secs. 21 & 22.
	Var. 20° East.
40.00	Set temp. $\frac{1}{4}$ Sec. corner.
79.60	Intersect E & W. line 20 lks. East of Old Cor. to Secs. 15, 16, 21 & 22. Set stone 8 x 9 x 10 ins. in old mound for cor. to Secs. 15, 16, 21 & 22, marked with