

Subdivisions, T. 2 N. R. 32 E.

Chains	
	8 ins. in the ground for U. R. Closing Corner, marked U.R.C.C. on E., S. 8 on N. and S. 17 on S. faces. Dug pits 18 x 18 x 12 ins. E. N. & S. from stone 5½ ft. dist. and raised a mound of earth 2 ft. high, 4½ ft. base over it.
40.00	Set stone 9 x 8 x 7 ins., 6 ins. in the ground for ¼ Sec. cor., marked ¼ on N. face. Dug pits 18 x 18 x 12 ins. E. & W. from stone 5½ ft. dist. and raised a mound of earth 1½ ft. high, 3½ ft. base alongside.
	Descend.
68.00	Gulch. Course N.E.
69.50	Enter creek bottom. Course N.W. and S.E.
79.12	McKay Creek runs N.W.
80.00	To corner to Secs. 8, 9, 16 & 17.
	Land, rolling. Dense cottonwood and thorn, 10.50 chains. Some grass. Soil, 2nd rate.
<hr/>	
	North on random bet. secs. 8 & 9. Var. 21° 30' East.
40.00	To old ¼ Sec. Cor. bet. Secs. 8 & 9, which is a mound of earth with pits; old post gone. Thence, South on true line.
39.00	Intersect U. R. bdy. Set a stone 12 x 11 x 10 ins., 8 ins. in the ground for U. R. Closing Corner. Marked U. R. C. C. on S. face, S. 8 on W. and S. 9 on E. faces. Dug pits 18 x 18 x 12 ins. S., E. & W. from stone 5½ ft. distant and raised a mound of earth 2 feet high, 4½ feet base over it.
40.00	To Corner to Secs. 8, 9, 16 & 17. Land, level. Soil, 2nd rate.
<hr/>	

-250