

E. bdy. T. 2 N.R. 33 E.

Chains		
80.00	Set stone 18 x 10 x 4 in. for corner to secs. 30, 31, 25 and 36. Land, steep and stony. Soil, 3rd rate.	-600
<p>North on East boundary of Sec. 25. Variation 21°30' East. Descend.</p>		
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits, trench &c., as per instructions.	
80.00	Set stone 14 x 8 x 8 in. for corner to secs. 24, 25, 19 & 30. Land, steep and rocky. Soil, 2nd rate. Foot of hill. Spring 300 links S.E.	-1000
<p>North on East boundary of Sec. 24. Variation 18°30' East.</p>		
3.00	Dry bed of creek, course N.W.	
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits, trench &c., as per instructions.	
80.00	Set post for corner to secs. 18, 19, 13 & 24 in mound of earth with charred stake, pits, trench &c., as per instructions. Land, gently rolling. Soil, good 2nd rate.	
<p>North on East boundary of Sec. 13, Variation 21° East.</p>		
27.50	Road bears E & W.	
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits, trench &c., as per instructions.	
80.00	Set post for corner to secs. 12, 13, 7 & 18 in mound of earth with charred stake, pits, trench &c., as per instructions. Land, gently rolling. Soil, 1st rate.	