

N. Bdry. T. 1, N.R. 33 E.

Chains	
40.00	Drove charred stake and made mound of earth for $\frac{1}{4}$ Section corner.
80.00	Set charred stake, made earth mound for corner to Secs. 3, 4, 33, 34. Land, level. Soil, 1st rate. Good grass.
<hr/> North 89° 50' East on the North boundary of Section 3. <div style="text-align: right;">Var. 18° 30' East.</div>	
40.00	Set basalt stone 16 x 14 x 12 for $\frac{1}{4}$ Section corner.
41.00	Tudie Willow, 20 links wide, flows N.W.
80.00	Set post and raised earth mound for corner to Secs. 2, 3, 34 and 35. Land, level. Soil, 1st rate. Good grass.
<hr/> North 89° 50' East on North boundary of Section 2. <div style="text-align: right;">Var. 19° East.</div>	
28.00	Wagon road, course NE & SW.
40.00	Set post and raised stone mound for $\frac{1}{4}$ Sec. corner.
45.50	Brook 4 lks., flows N.W.
80.00	Set basalt stone 18 x 16 x 14 for cor. to secs. 1, 2, 35 & 36. First half mile, level; 2d half, hilly. Good grass. Soil, 2nd rate.
<hr/> North 89° 50' East on North boundary of Section 1. <div style="text-align: right;">Var. 19° East.</div>	
40.00	Set basalt stone 14 x 14 x 12 for $\frac{1}{4}$ Sec. corner.
80.00	To corner to Townships 1 & 2 North Ranges 33 & 34 East Willamette Meridian.
<hr/> May 2, 1871.	