

## Subdivisions, T. 2 N., R. 33 E.

## Chains

East on random between Secs. 24 & 25.

Var. 21° 30' East.

40.00 Set temporary  $\frac{1}{4}$  Sec. corner.

80.08 Intersected N & S line 17 lks. S of corner.

S. 89° 53' West on true line.

40.04 Set stone 14 x 12 x 4 for  $\frac{1}{4}$  Sec. corner.

80.08 To corner.

Land, rolling.

Soil, 2nd rate. Good grass.

North between Secs. 23 & 24.

40.00 Set post and made mound of earth for  $\frac{1}{4}$  Sec. corner.

80.00 Set post and made mound of earth for corner to Secs.

23, 24, 13 & 14.

Land, level.

Soil, 1st rate. Good grass.

East on random between Secs. 13 & 24.

Variation 21° East.

40.00 Set temporary  $\frac{1}{4}$  Sec. corner.

79.90 Intersected N & S line 14 N of corner.

N. 89° 54' W. on true line.

22.45 Brook, 8 lks., flows N.W.

39.95 Set stone 14 x 14 x 9 for  $\frac{1}{4}$  Sec. cor.

79.90 To corner.

Land, level.

Soil, 1st rate. Good grass.

North between Secs. 13 & 14.

12.50 LaGrande and Pendleton road, course E & W.

40.00 Set post and made mound of earth for  $\frac{1}{4}$  Sec. corner.

80.00 Set post and made mound of earth for cor. to Secs. 13,

14, 11, 12.

Land, level.

Soil, 1st rate. Good grass.